



## EPSILON CORPORATE HQ

Irving, Texas

FSG was awarded the contract to provide and install audio/visual systems for Epsilon's new corporate offices located in Irving, Texas.

**Owner**  
Epsilon Corporate HQ

**Contract Type**  
Technology

**Contract Amount**  
\$673,000

**Electrical Contractor**  
FSG

### CHALLENGE

FSG was awarded the contract to provide and install audio/visual systems for Epsilon's new corporate offices located in Irving, Texas. The project called for full audio/visual capabilities for some 68 rooms and public spaces. The scope included large and medium-sized conference rooms, meeting rooms, operations center, a Customer Experience Center, and training rooms. In addition, a sound-masking system would be provided and installed.

### SOLUTION

The standard meeting room configuration included multiple 60" to 80" LCD displays, with video and audio routed from table-top boxes to the displays, as well as wireless capability. The Customer Experience Center and adjacent 16-seat presentation room called for an 80" LCD display wired for laptop computer control via table boxes and wireless. The audio/visual system in the Operations Center consisted of six commercial-grade Planar 55" wall-mounted flat screens which display data in Epsilon's mission critical 24/7 control room. Ceiling-mounted projectors were installed in the divisible training rooms. FSG continues to service and support the Epsilon offices, and provides ongoing updates to their systems.

For more information about FSG  
Visit [WWW.FSGI.COM](http://WWW.FSGI.COM)

